Stone Columns and Tensioned Anchors to Completely Eliminate Tunnels Trough Settlements

Ampeglio Diego Garini

ITALCONSULT, Rome 00161, Italy

Abstract: The complex tunnelling constructive environment in urban area in similar green field situations is faced through analytical evaluations in order to control the design calculation process and subsequently manage the interventions techniques with the aim of totally reducing the typical settlements trough above the tunnel either during the construction stage or during the serviceability stage. Recently, the author has proposed an operative and mathematical method by an opportune choice of tensioned anchors to control the tunnel lining settlements. In order to completely eliminate the remainder typical soft soil trough which is normal to the line of the tunnel, it is here proposed to use and properly calculate the interventions of stone columns by the SAVE (silent, advanced, vibration-erasing) Compozer method, in combination with the anchorages.

Key words: Anchorages, SAVE Compozer method, stone columns, tunnel lining, tunnel trough.

1. Introduction

The problem of the trough settlements above tunneling excavations is of great concern in urban areas whether we have an intensively-built buildings in metropolitan area or we face important avenues in green field similar conditions. Recently, Garini [1] has studied an analytical strength of material solution to know better the internal forces in tunnel circular lining arch beams and so to correctly intervene to stop the lining convergences via some tensioned anchors. A brief resume of this work is also available in Ref. [2].

Main objectives of the analytical solution of Ref. [1] are:

- analytically following the internal forces along the circular tunnel in order to punctually define the stress-strain state, due to the overlying urban soil-foundations loads;
- operatively impeding deflections in the anchorage points or accepting a minimum settlement;
- intervening on the lining thickness and consequently on its flexural rigidity in order to limit

the remainder part of settlements along the inter-anchorages spans.

In such a complex urban tunnels environment, either in green field or in soil-structure interaction condition, there persists a certain lack of precision in the design—controlling process, the construction interventions and the connected ground movements.

In this paper, we focus in particular on urban area green field similar conditions where we can consider to alleviate via SAVE (silent, advanced, vibration-erasing) Compozer stone columns the typical tunnel induced trough with a triple action: The first action is to mitigate immediate elastic, primary and secondary consolidation settlements; The second action is to mitigate subsidence phenomena [3]; and last but not least, to reduce the remainder effect of the lining deflections, by using the inter-spanning space among the anchorages. In this way, the typical tunnel hole cavity contraction problem is faced via an equivalent load-settlement phenomena by a representation of forced settlement—non-compensated load with reference to the dual case of forced load-induced settlement.

Corresponding author: Ampeglio Diego Garini, consulting engineer, research fields: geotechnics and soil-structure interaction. E-mail: adiego.garini@alice.it.

Moreover, we state some appropriate design—construction management decisions with the aim to almost totally eliminate the abovementioned settlement trough with the intervention of SAVE Compozer applications.

1.1 Typical Tunnel Trough Settlements Problems and Related Evaluations

The tunnel construction under monumental buildings has induced both scholars and professionals in the last two decades [4-6] to accurately study the typical tunnel trough due to soil structure interaction.

Important case histories are examined in Refs. [7, 8]. In particular in Ref. [7], due to operational constraints, it was possible to intervene only with HJG (horizontal jet grouting) ahead of the tunnel crown and without vertical jet grouting ahead of the tunnel face. And in the crossing centerline under two buildings, there have been encountered important green field settlements of about 0.2 m in relatively soft lightly overconsolidated silty clays and clayey silts (the undrained cohesion of T1 formation, a medium to high plasticity clayey silt and silty clay with high fines: $S_u \approx 100$ kPa) interbedded with lenses of sandy silts and silty sands (T2 formation).

1.2 Stone Column/SAVE Compozer Applications

Stone columns are a typical soil improvement technique for the construction of compacted gravel/sand columns in soft soils, either sandy or clayey that consists in a vibro-replacement method in a manner similar to vibroflotation, namely by means of a vibrator containing an eccentric weight to give an horizontal vibration.

A recent typical vibro stone columns application is reported in Ref. [9], where soft ground was improved to support heavy load of 500 kPa for an oil and gas petroleum structure fabrication in Vung Tau in Vietnam, especially as a means of bearing capacity increase.

SAVE Compozer has a casing pipe rotating, driven

by a vibration unit with the very important advantage for urban and residential areas of no vibration and low noise.

2. Analytical Evaluations

2.1 Equivalent Load Settlement Calculations

As indicated in Ref. [10], briefly described also in Ref. [11], we can get the dimension of the immediate settlement necessary stone column area A_c with the following two equations:

$$\frac{p_c}{p_s} = \frac{1 + \frac{E_c}{E_s} K_s \ln \frac{a}{r_0}}{2 \frac{E_c}{E_s} K_c \ln \frac{a}{r_0}} \quad (1)$$

$$p_0 A = p_c A_c + p_s A_s \quad (2)$$

where, A , p_0 are the footing area per compaction column and the average load intensity, E_c , A_c , p_c are respectively the elastic modulus, the area and the bearing stress on stone column and E_s , A_s , p_s are respectively the elastic modulus, the area and the bearing stress on untreated soil, while K_c and K_s are the coefficients of earth pressure respectively for the stone columns and, for untreated soil and finally, r_0 is the stone column radius and

$$a = \sqrt{\frac{A}{\pi}} \quad (3)$$

With Eqs. (1)-(3), once the elastic improved soil modulus is known, it is possible to figure out the stone columns soil improvement design parameters for a certain building or highway road/railway embankment footing to construct and get an opportune grid of stone columns beneath the desired foundation to stabilize as bearing capacity and, first of all, as a differential settlements problem.

2.2 Immediate and Creep Settlement Calculations—Pure Friction Resistant Soils

So we can consider to have a remainder average tunnel lining settlement at depth H (plus the semi circumference centroid $(R/\pi) \times (\pi - 2)$) of the tunnel underneath the soil surface as shown in Fig. 1, where

Fig. 1 The remainder radius R , semi-circular tunnel average deflection ρ at depth H to back calculate an equivalent surface pressure p_0 via the Schmertmann [12] method to figure out the stone columns dimensioning. The tunnel is tensioned by two 60° inclined anchor strands.

typically the anchorages could be 2 m or 3 m each of tunnel length and stone columns in between those strands rows, and then we will have the corresponding value of p_0 , for example, in pure friction resistant soils, from the Schmertmann [12] method:

$$p_0 = \frac{\rho}{\int_0^{2D} \frac{I_z}{E} dz} \quad (4)$$

where, ρ is the surface settlement identified in this case with the average remainder tunnel lining deflection as visible in Fig. 1 and so hypothesizing that the soil moves rigidly downward, D is the corresponding surface foundation diameter and I_z , as known, is given by the following equations:

$$I_z = \alpha \frac{z}{D} \quad 0 \leq z \leq \frac{D}{2} \quad (5)$$

$$I_z = \frac{2}{3} \alpha \left(1 - \frac{z}{2D}\right) \quad \frac{D}{2} \leq z \leq 2D \quad (6)$$

with α typically equal to 1.2.

The Schmertmann method [12] makes possible to systematically calculate the static settlement of isolated, rigid, concentrically loaded shallow foundations over non cohesive soils, especially sands.

The method employs elastic half-space theory in a simplified form and uses the static cone bearing capacity as a practical means for determining in-situ compressibility and includes a simplified distribution of vertical strain under a foundation, expressed in the

form of a strain influence factor, a typically $2D-0.6$ (or $0.5 + (p_0/\sigma'_{vp})^{0.5}$) I_z distribution as in Ref. [13], where, σ'_{vp} is the vertical stress at the depth of maximum influence.

Finally, Schmertmann [13] also suggested to take into account the foundation embedment by the coefficient C_1 and creep by the coefficient C_2 through Eqs. (7) and (8):

$$C_1 = \left[1 - \frac{0.5\sigma'_v}{p_0}\right] \geq 0.5 \quad (7)$$

where, σ'_v is the effective stress at the embedment depth,

$$C_2 = \left[1 + 0.2 \log\left(\frac{t}{0.1}\right)\right] \quad (8)$$

where, t is expressed in years.

2.3 Soil Shear Beam Bridging the Tunnel—Undrained Maximum Deflection-Cohesive Soils

With reference to the case described in Ref. [7] and above briefly recalled, where we have homogenous lightly overconsolidated clay with probably the undrained elastic modulus $E_u = 600 S_u \approx 60$ MPa (for plasticity index $PI = 30\%$) and the Poisson ratio $\nu = 0.4$, we can imagine to bridge ($q = \gamma S$ is the uniformly distributed load and S is the beam cross section) the tunnel with an elastic constant squat shear beam, whose span is $2 \times 33 \text{ m} \times 2/3$ (parabolic average evaluation on the tunnel trough of half length of 33 m) and because from De Saint Venant theoretical beam problem, we have constant shear stress for the entire S , namely, as GK is the shear rigidity, hypothesizing full plasticization for the entire cross section, $K = S$ (with a rectangular shear stress diagram), we can figure out the maximum elastic settlement, which is indeed 0.2 m, as measured in situ, by the following equation:

$$v_{\max} = \frac{ql^2}{8GK} = \frac{ql^2}{8GS} = \frac{\gamma l^2}{8G} \quad (9)$$

where, q is the beam uniformly distributed load, γ is the soil specific weight and G is the soil-beam shear modulus.

In the same way, for the centerline S-TE, we can reconstruct the other green field cases recalled in

Ref. [7] during the not supported tunneling and shown in Table 1 and Figs. 2 and 3.

Table 1 Comparison between back analyzed elastic not supported trough settlements with measured settlements in Ref. [7].

Tunnel face distance d (m)	γ (kN/m ³)	E_u (kN/m ²)	Poisson ratio ν	Reconstructed span squat soil shear beam l (m)	Shear factor χ	Calculated with Eq. (10) $V_{\max}$ (m)	Measured $V_{\max}$ (m)
+31	18.00	60,000	0.4	44.0	1.0	0.203	0.20
+5	18.00	60,000	0.4	44.0	1.0	0.203	0.17
-7	18.00	60,000	0.4	34.7	1.0	0.126	0.11
-19	18.00	60,000	0.4	18.7	1.0	0.037	0.03
+31	18.00	72,000	0.4	44.0	1.2	0.203	0.20
+5	18.00	72,000	0.4	44.0	1.2	0.203	0.17
-7	18.00	72,000	0.4	34.7	1.2	0.126	0.11
-19	18.00	72,000	0.4	18.7	1.2	0.037	0.03
+31*	18.00	72,000	0.4	44.0	1.2	0.203	0.20
-5*	18.00	72,000	0.4	44.0	1.0	0.169	0.17
-7*	18.00	72,000	0.4	34.7	1.0	0.105	0.11
-19*	18.00	72,000	0.4	18.7	1.0	0.030	0.03

* These values correspond to the best fit interpretations.

Fig. 2 Comparison between back analyzed elastic not supported trough settlements with measured settlements in Ref. [7] tunnel trough and related squat shear beam when the tunnel face is at -19 m from the centerline. The shear beam force plasticizes the soil at the centerline so a shear factor $\chi = 1$ must be used to fit the measured data.

Fig. 3 Comparison between back analyzed elastic not supported trough settlements with measured settlements in Ref. [7] Tunnel Trough and related squat shear beam when the Tunnel face is at -7 m from the centerline. The shear beam force plasticizes the soil at the centerline so a shear factor $\chi = 1$ must used to fit the measured data.

This obviously means that in case the construction of the stone columns had been possible, we could have reduced this important maximum settlement up to about 4 cm , as indicated in the following, and

ultimately stopped it by means of opportune timely construction of the anchorages.

In case of non plasticized cross sections above the tunnel and rearranging $S_u = 120 \text{ kPa}$ as indeed

considered in Ref. [7], we in general have:

$$v_{\max} = \frac{ql^2}{8GK} = \frac{ql^2}{8G\left(\frac{S}{\chi}\right)} = \frac{\gamma^2}{\left(\frac{8G}{\chi}\right)} \quad (10)$$

where, χ is the shear factor and is 1.2 for a rectangular cross section, namely a parabolic shear stress diagram, and so we figure out the same deflections as before as visible in Table 1, but if we hypothesized that only the case of maximum deflection is in an elastic state, namely we had a plastic condition when the tunnel face is still far from the centerline S-TE or has just underpassed it, then we should get the perfect coincidence between the calculated deflections and the measured values, as visible in the last four rows of Table 1.

2.4 Some Stone Columns Soil Improvement Scenarios

We can imagine the following scenario $p_c/p_s = 10$, $A_c/A = 0.1$, so $A_s/A = 0.9$. Then from Eq. (1), $p_0/p_s = 1 + 0.9 = 1.9$ and so $S_s = S_0/1.9$, where S_s and S_0 are respectively the settlement of the improved soil and that of the not improved soil.

In the same way, we can imagine to design a second scenario with $p_c/p_s = 20$, $A_c/A = 0.2$. In this case from Eq. (1), we shall have $p_0/p_s = 4.0 + 0.8 = 4.8$ and so $S_s = S_0/4.8$, i.e., with the final settlement reduced by about 80%. With this value, we can find that it is practically possible to totally eliminate any remainder tunnel lining settlement.

2.5 Operative Approach

So in general, we could face the problem of tunnel lining settlements regarding each singular urban area layout. In case of an intensively-buildings built area, we could approach the problem when possible by tensioned anchors if it will not be more practical adopting compensation grouting or other means to retain the soft soil thrusts.

Also, in case of partial green field similar environment in urban areas, we can adopt SAVE Compozer stone columns to eliminate the remainder

tunnel lining settlements, if already adopted a tensioned anchors solution with the decisive advantage to eliminate, as shown above, every tunnel lining settlements and contemporarily limiting primary and secondary soil consolidation settlements above and around the tunnel along with limiting subsidence phenomena.

3. Discussions

The settlements trough due to underground tunneling in soft soils, must be faced with different design and construction stages:

(1) Firstly, the drained immediate elastic settlements may be captured by the equivalent settlement procedure from Schmertmann method as indicated previously, while the undrained immediate elastic settlements above the tunnel may be easily individuated in case of homogeneous soil squat beam, spanning the 2/3 of the tunnel not supported (apart from a horizontal jet grouting canopy in Ref. [7], due to operational constraints and useful to withstand the squat shear beam reactions) double distance between the face and the outward trough limit;

(2) Secondly, timely intervention with tensioned anchorages lining strengthening can importantly contribute to withstanding the abovementioned soil squat beam uniformly distributed load $q = \gamma S$ during the primary consolidation process as well for both the drained and the undrained creep deformation behaviour. If tunnel lining calculations are done according to Ref. [1], using the entire load q plus the building added pressures, and no settlements are allowed by the anchorages foundation the only remainder settlements to be reduced are the lining anchorages interspan deflections. Otherwise, if anchorages lining supports settlements are permitted, the remainder, either elastic or consolidation settlements to be reduced by the preventive stone columns intervention, is greater;

Thirdly, primary and secondary consolidation settlements will act, first of all, because of the load not

compensated by the anchorages.

Anyway, if we have not preventive intervention with stone columns to importantly reduce the deformation field and timely tunnel anchorages construction, the global settlement field could be remarkably important.

4. Conclusions

A method to figure out the equivalent surface pressure p_0 in pure friction—resistant soils, to totally eliminate the remainder lining settlement of a circular tunnel reinforced by tensioned anchors has been presented via the analytical procedure by Baumann & Bauer [10] and then back-calculating the surface settlement by the Schmertman method [12].

This method is also applicable in cohesive soils, to limit the immediate elastic settlements along with successive primary consolidation and creep deformations when due to the weakness of the tunnel protective interventions, the soil overburden span and the advancing tunnel hole with undrained settlements proportional to $1/E_u$, while should exploit a huge advantage from a stone columns intervention in similar greenfield areas.

Stone columns intervention is a practicable construction technique in similar greenfield condition and can especially help to concentrate their action on the entire available potential trough area either to prevent important not sufficiently supported tunnel elastic settlement during tunneling or to greatly diminish and almost eliminate any remainder settlement, when timely intervention of lining anchorages is provided.

SAVE Compozer stone columns technique has the important advantage for urban and residential areas of no vibrations and low noise.

A series of tunneling construction techniques such as compensation grouting and a jet grouting canopy, tunnel lining anchorages can be used in soft soils in combination with stone columns intervention. But it shows the importance of using tunnel lining

anchorages because they permit a correct management of stress-strain soil and lining analytical design calculations, along with an opportune areal distribution of stone columns and an exact scheduling of the times of the tunnel lining support interventions, to control at all the deformation field above the tunnel, whether during the construction stage or during the work serviceability.

Future research is possible to further capture via analytical and/or numerical design calculation control, both primary and secondary consolidation phenomena, and, in addition, any subsidence prone situation that could severely act on the tunnel deformation field.

References

- [1] Garini, A. D. 2012. "An Analytical Method to Control the Tunnel Lining Settlements." In *Geotechnical Aspects of Underground Construction in Soft Ground*, edited by Viggiani, G. London: Taylor & Francis Group, 471-5.
- [2] Jacobsz, S. W. 2012. "Numerical and Physical Modeling of Tunnels and Deep Excavations." In *Geotechnical Aspects of Underground Construction in Soft Ground*, edited by Viggiani, G. London: Taylor & Francis Group, 79-85.
- [3] Ng, C. W. W., Li, Q., and Liu, G. B. 2012. "Long-Term Tunnel Settlements Mechanisms of Metro Line 2 in Shanghai." In *Geotechnical Aspects of Underground Construction in Soft Ground*, edited by Viggiani, G. London: Taylor & Francis Group, 21-36.
- [4] Mair, R. J., and Taylor, R. N. 1997. "Bored Tunneling in the Urban Environment." In *Proceedings of 14th International Conference on Soil Mechanics and Foundation Engineering*, 2353-85.
- [5] Potts, D. M., and Addenbrooke, T. I. 1997. "A Structures Influence on Tunneling Induced Ground Movements." In *Proceedings of Institution of Civil Engineers—Geotechnical Engineering*, 109-25.
- [6] Franzius, J. N., Potts, D. M., and Burland, J. B. 1997. "The Response of Surface Structures to Tunnel Construction." In *Proceedings of the Institution of Civil Engineering—Geotechnical Engineering*, 3-17.
- [7] Farrell, R. P., Mair, R. J., Sciotti, A., Pigorini, A., and Ricci, M. 2012. "The Response of Buildings to Tunneling: A Case Study." In *Geotechnical Aspects of Underground Construction in Soft Ground*, edited by Viggiani, G. London: Taylor & Francis Group, 21-36.
- [8] Murphy, J., Gaynor, S., and Laefer, D. F. 2010.

- “Predicted Tunnel-Induced Settlement and Damage to Findlater’s Church with Respect to Freefield and Constructed Side Considerations.” In *GeoFlorida Conference Proceedings: Advances in Analysis, Modeling & Design*, 1690-9.
- [9] Le, H. Q., Yee, Y. W., Minh, T. N., Leung, C. F., and Shen, R. F. 2013. “Application of Vibro Stone Columns for a Fabrication Yard in Vietnam, Advances in Geotechnical Infrastructures.” In *Proceedings of 18th Southeast Asian Geotechnical Conference cum Inaugural AGSSWA Conference*, 213-20.
- [10] Baumann, V., and Bauer, G. E. A. 1974. “The Performance of Foundations on Various Soils Stabilized by the Vibro-Compaction Method.” *Canadian Geotechnical Journal* 11: 509-30.
- [11] Mitchell, J. K. 1981. “Soil Improvement—State of the Art Report.” In *Proceedings of the 10th ICSMFE (International Conference of Soil Mechanics and Foundation Engineering)*, 509-65.
- [12] Schmertmann, J. H. 1970. “Static Cone to Compute Static Settlement over Sand.” *Journal of the Soil Mechanics and Foundations Division* 96 (3): 1011-43.
- [13] Schmertmann, J. H., Hartmann, P., and Brown, P. H. 1978. “Improved Strain Influence Factor Diagrams.” *Journal of the Geotechnical Engineering Division* 104 (8): 1131-5.